

**ELLINGTON DEPARTMENT OF PUBLIC WORKS
VETERAN'S MEMORIAL ELLINGTON GREEN**

ADDENDUM #1

June 11, 2021

The following Addendum #1 forms a part of the Contract Documents and modifies the original Project Manual including specifications and Drawings for the project entitled "Veteran's Memorial Ellington Green" located in Ellington, Connecticut.

This Addendum #1 consists of a total of 14 pages, including the following attachments:

1. Revised Project Drawing Sheets 1 through 4 (4 pages)
2. Revised Bid Form (8 pages)

ITEM AD1-1 **PROJECT DRAWINGS**

The Project Drawings have been revised to address recent comments received by the Connecticut Department of Transportation (DOT). The attached revised Project Drawings (Sheets 1 through 4) with the revision date June 9, 2021 will replace the prior Project Drawing pages (Sheets 1 through 4) and be the basis for the Bid. The following is a summary of the revisions:

1. Elimination of the proposed improvements to provide a pedestrian connection between the memorial and the existing sidewalk on the north side of Maple Street (Rte. 140) including a section of new sidewalk, replacement of existing sidewalk, curb ramps, crosswalk, and pedestrian crossing signs.
2. Modifications to the concrete sidewalk detail to bring it into conformance with the DOT Standard concrete sidewalk detail.
3. Add a note to call for a break in the centerline and edge lines at the proposed crosswalk.
4. Add a note to call for relocation of the Route Marker Sign on Main Street if it should interfere with visibility of the new pedestrian crossing sign.

ITEM AD1-2 **BID FORM - 00410**

REPLACE the existing form with the attached revised BID FORM reflecting the revisions to the Project Drawings discussed above. (Please note that the table for Unit Price Work provided in Section 5.01.A of the AGREEMENT, will be modified to reflect the same changes to the BID FORM at the time of issuance of the completed form to the successful bidder.)

ITEM AD1-3 **SUMMARY OF WORK – 01200**

REPLACE paragraph 1.03.B.9 with the following to reflect the elimination of the demolition of granite curbing and the addition of the need to eradicate existing line striping at the proposed crosswalk:

9. Eradicate existing line striping to allow for the new crosswalk striping.

**ELLINGTON DEPARTMENT OF PUBLIC WORKS
VETERAN'S MEMORIAL ELLINGTON GREEN**

REPLACE paragraphs 1.03.B.13 and 14 with the following to reflect the elimination of the crosswalk on Maple Street:

13. Furnish and install paint striping for one (1) new crosswalk.
14. Furnish and install two (2) new pedestrian crossing signs (MUTCD W11-2) with diagonal arrows (MUTCD W16-7PL)

ITEM AD1-4 MEASUREMENT & PAYMENT – 01250

REPLACE paragraph 1.03.I with the following to reflect the elimination of the demolition of granite curbing and the addition of the need to eradicate existing line striping at the proposed crosswalk:

- I. Eradicate Existing Line Striping:
 1. Payment: Payment will be made at the Contract unit price per lineal foot for “Eradicate Existing Line Striping” which shall include removal, materials, equipment, tools, labor and work incidental thereto.
 2. Measurement: Lineal Foot (LF) completed and accepted.

ITEM AD1-5 PORTLAND CEMENT CONCRETE PAVEMENT

CLARIFICATION of paragraph 1.03.D. which states “Installer shall have at least two years’ experience with projects of similar scope and quality.” The two years of experience can be satisfied with general concrete sidewalk construction experience. However, the installer shall demonstrate some experience with stenciled concrete and provide at least one reference and location where prior stenciled concrete work can be viewed.

END OF ADDENDUM #1